

**PROJECT PROFILE | MALL OF AMERICA HOTEL EXPANSION | MINNEAPOLIS, MN**

**ARCHITECT**

DLR Group  
Minneapolis, MN 55402  
612-977-3500

**VAPROSHIELD REPRESENTATIVE**

Mike Herbst  
Environmental Building Products  
Excelsior, MN 55331  
952-380-0730  
[mherbst@ebpmn.com](mailto:mherbst@ebpmn.com)

**CONTRACTOR**

Mortenson Construction  
Minneapolis, MN 55422  
763-522-2100

**INSTALLER**

Custom Drywall, Inc.  
St. Paul, MN 55103  
651-488-0533

**PRODUCT(S)**

**WRAPSHIELD**<sup>®</sup> SA Self-Adhered Water Resistive Vapor Permeable Air Barrier Sheet

**PROJECT DESCRIPTION**

The \$325 million Mall of America expansion project includes a 342-room JW Marriott hotel, an office tower, high-end retail, a new dining area, and an underground parking ramp. The initial phase broke ground in March 2014 and features over 190,000 sq. ft. of WrapShield SA Self-Adhered Water Resistive Vapor Permeable Air Barrier Sheet installed on the JW Marriott hotel.

With Minnesota's harsh winters, WrapShield SA Self-Adhered is an ideal choice because it can be installed in temperatures as low as 20°F (-6°C), helping to prevent weather delays and allowing project construction to carry on as scheduled.

WrapShield SA Self-Adhered key features:

- No primer is required
- Zero VOC's, (no off-gassing)
- Low Temperature Applications
- Fire Rated, Class A to ASTM E 84
- 6 Months UV & Climate Exposure



*Over 190,000 sq. ft. of WrapShield SA Self-Adhered Water Resistive Vapor Permeable Air Barrier Sheet was installed on the JW Marriott, which is part of the \$325 million Mall of America expansion project.*



*With its durability and all climate friendly installation, WrapShield SA Self-Adhered can withstand the harsh Minnesota winters during construction.*



*Stay up-to-date on the Mall of America hotel expansion project with views from the Mortenson Construction webcam:  
<http://oxblue.com/open/mortenson/moa1c>*